BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

MODIFIED SCHEDULE - B

Package-5 (1) Improvements of Road Adjacent to Yelahanka Lake from Kenchenahalli to Chowdeshwari Temple in Ward No.02 (2) Improvements and Asphalting to New post office main road and cross roads in ward No. 01 (3) Improvements and Asphalting to Sugappa layout cross roads in ward No. 01 (4) Improvements and Asphalting to Shanimahathma swamy temple road and Surabhi layout 2nd main and cross roads in ward No. 01 (5) Asphalting to Balance roads in A & B sector of Yelhanka New Town in Ward No. 04

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. R Lokesh	
				In figures	In words
1	2306.25	Removing B.S slabsand stacking etc complete	Sqm	68.35	Rupees Sixty Eight And Paise Thirty Five Only
2	2148.90	Refixing stone slabs of drains and pointing in C.M	Sqm	83.78	Rupees Eighty Three And Paise Seventy Eight Only
3	13054.63	KSRRB 200-8. Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials labour charges complete as per specifications. MORTH / Chapter 2 ---- Including all lead lifts loading unloading transportation labour hire charges of machinery curing for concrete works cost and convene of all material and all other such incidental charges necessary for successful completion of works as per the detailed technical specification and direction of Engineer in charge of this work	Sqm	9.92	Rupees Nine And Paise Ninety Two Only
4	0.00	KSRRB 200-1. Cutting of trees girth from 300mm to 600mm including cutting of trunks, branches and removal of stumps roots stacking of serviceable materials earth filling in the depressions / pit, labour charges complete as per specifications.	Each	208.35	Rupees Two Hundred Eight And Paise Thirty Five Only
5	0.00	Removing stumps, tree roots, roots of bamboo cluster etc.,, with 8.2.2 grith above 1.50 m and upto 3.00 m including excavation, stacking materials neatly and levelling area etc	Each	91.52	Rupees Ninety One And Paise Fifty Two Only
6	0.00	Dismantling Mangalore tiles roof and stacking the material within a radius of 50 meters. including cost of materials, labour, HOM complete as per specifications.	Sqm	68.35	Rupees Sixty Eight And Paise Thirty Five Only
7	30.36	Dismantling of existing structure like Culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding whereever necessary, sorting the dismantled material, disposal of unserviceble material and stacking the serviceble material and stacking the serviceble material with all lifts complete with all lifts complete as per specifications. C prestressed / Reinforced cement concrete grade M-20 & above	cum	1126.65	Rupees One Thousand One Hundred Twenty Six And Paise Sixty Five Only
8	0.00	Demolishing stone rubble masonry manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material to the appropriate disposal area as per direction of Engineerin-charge. In cement mortar	cum	225.99	Rupees Two Hundred Twenty Five And Paise Ninety Nine Only
9	0.00	Dismantling burnt brick masonry in clay mortar/lime mortar/cement mortar and stacking the bricks within a radius of 50m and removing the debris to a distance upto 200m. including cost of materials, labour, HOM complete as per specifications	Sqm	171.97	Rupees One Hundred Seventy One And Paise Ninety Seven Only
10	0.00	Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200m (within average thickness of 15 cms). including cost of materials, labour, HOM complete as per specifications.	Sqm	60.63	Rupees Sixty And Paise Sixty Three Only
11	905.86	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	cum	90.40	Rupees Ninety And Paise Forty Only

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. R Lokesh	
				In figures	In words
12	13461.84	KSRRB M300-14. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in ccordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications.	cum	50.71	Rupees Fifty And Paise Seventy One Only
13	127.31	KSRRB 300-8. Excavation in hard rock by chiselling and / or wedging where blasting is prohibited for formation of roads including stacking to uniform line and level including cost of all labour complete as per specifications. (with all lead and lift)	cum	1243.51	Rupees One Thousand Two Hundred Forty Three And Paise Fifty One Only
14	143.39	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	cum	5562.71	Rupees Five Thousand Five Hundred Sixty Two And Paise Seventy One Only
15	165.59	"KSRRB M2100-15.2. Providing and laying Reinforcement Cement Concrete M20 with OPC @ 320 kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplasticizer @3lts confirming to IS9103-1999 Reaffirmed-2008 in Open Foundation complete as per Drawing and Technical Specifications including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. MORTH Specification No. 1500,1700 & 2100	cum	6626.53	Rupees Six Thousand Six Hundred Twenty Six And Paise Fifty Three Only
16	7.83	KSRRB M2200-6. Providing T.M.T. steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per disign (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specification. MORTH Specification No.1600 & 2200	Ton	66813.16	Rupees Sixty Six Thousand Eight Hundred Thirteen And Paise Sixteen Only
17	236.32	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2	Sqm	323.00	Rupees Three Hundred Twenty Three Only
18	91.94	Providing and fixing precast covering slab made out of CC 1:2:4 with 100 cm thick and Finishing cutting including form work curing including cost of all materials, labour, unloading, lead and lift transportation etc, complete	Sqm	1976.00	Rupees One Thousand Nine Hundred Seventy Six Only
19	0.00	Providing chain link fencing 50mm size of 8 guage properly stretched between existing rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the, directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint, including cost of materials, labour, HOM complete as per specifications.	Sqm	726.48	Rupees Seven Hundred Twenty Six And Paise Forty Eight Only
20	0.00	Providing barbed GI wire fencing of 12x12 gauge drawn into stone pillars or iron pillars including drawing in holes wherever necessary excluding the cost of pillars but including the cost of barbed wire and binding wire etc., including cost of materials, labour, HOM complete as per specifications.	mt	30.87	Rupees Thirty And Paise Eighty Seven Only
21	0.00	Providing and fixing to wall, ceiling and floor unplasticised PVC 10.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials, labour charges, HOM and testing complete as per specifications.	mt	120.16	Rupees One Hundred Twenty And Paise Sixteen Only
22	0.00	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after throughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Sqm	76.07	Rupees Seventy Six And Paise Seven Only

Scanned by TapScanner

				Approved Rates of Sri. R Lokesh	
	Quantity	Item Name	Unit	In figures	In words
		In figures ... In words ... Sixty Eight			
23	28.35	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar & stone hammerd dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, HOM, curing complete as per specifications. KBS 5.1.13	cum	4615.75	Rupees Four Thousand Six Hundred Fifteen And Paise Seventy Five Only
24	6.30	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, for coping. Including cost of all materials, labour, HOM, curing complete as per specifications.Specification No. KBS 4.1, 4.2	cum	5998.16	Rupees Five Thousand Nine Hundred Ninety Eight And Paise Sixteen Only
25	49.50	Providing and fixing precast covering slab 250 cm thick made out of CC 1:2:4 and jelly 20mm Down size withg steel reinforcement including form work curing including cost of all materials, labour, unloading, lead and lift transportation etc, complete	Sqm	5529.68	Rupees Five Thousand Five Hundred Twenty Nine And Paise Sixty Eight Only
26	12900.00	KSRRB M300-53. Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of modified proctors density. MORTH Specification No. 305 ---- Including all lead lifts loading unloading transportation labour hire charges of machinery curing for concrete works cost and convene of all material and all other such incidental charges necessary for successful completion of works as per the detailed technical specification and direction of Engineer in charge of this work	cum	332.92	Rupees Three Hundred Thirty Two And Paise Ninety Two Only
27	16367.78	KSRRB 300-Compaction KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. MORTH / Chapter 3 ---- Including all lead lifts loading unloading transportation labour hire charges of machinery curing for concrete works cost and convene of all material and all other such incidental charges necessary for successful completion of works as per the detailed technical specification and direction of Engineer in charge of this work	Sqm	5.51	Rupees Five And Paise Fifty One Only
28	3789.43	Construction of granular sub-base Grading-Vas Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98% proctor density, complete as per specifications. Clause 401 of MORTH V Revision ---- Including all lead lifts loading unloading transportation labour hire charges of machinery curing for concrete works cost and convene of all material and all other such incidental charges necessary for successful completion of works as per the detailed technical specification and direction of Engineer in charge of this work	cum	1731.87	Rupees One Thousand Seven Hundred Thirty One And Paise Eighty Seven Only
9	6370.57	KSRRB M400- Wet Mix Macadam KSRRB M400-17. Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH Specification No. 406 ---- Including all lead lifts loading unloading transportation labour hire charges of machinery curing for concrete works cost and convene of all material and all other such incidental charges necessary for successful completion of works as per the detailed technical specification and direction of Engineer in charge of this work	cum	1838.80	Rupees One Thousand Eight Hundred Thirty Eight And Paise Eighty Only

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. R Lokesh	
				In figures	In words
30	8673.46	Cleaning the existing black topped surface with brooms soft brushes and finally dusting with old gunny bags and or compresses air to receive bituminous treatmentincluding cost bof all materials labour HoM of machineries complete as per specification	Sqm	3.30	Rupees Three And Paise Thirty Only
31	17393.36	KSRRB M500-6. Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. MORTH Specification No. 502 ---- Including all lead lifts loading unloading transportation labour hire charges of machinery curing for concrete works cost and convene of all material and all other such incidental charges necessary for successful completion of works as per the detailed technical specification and direction of Engineer in charge of this work	Sqm	28.66	Rupees Twenty Eight And Paise Sixty Six Only
32	36396.49	KSRRB M500-10. Providing and applying tack coat using 80/100 grade bitumen(VG10) in boiler fitted with spray set distributor at the rate of 0.25 kg per sqm on the existing prepared bituminous surface (primed surface) cleaned with mechanical broom. complete as per specifications. Clause 503 of MORTH V revision ---- Including all lead lifts loading unloading transportation labour hire charges of machinery curing for concrete works cost and convene of all material and all other such incidental charges necessary for successful completion of works as per the detailed technical specification and direction of Engineer in charge of this work	Sqm	22.46	Rupees Twenty Two And Paise Forty Six Only
33	858.45	KSRRB M500-17. Providing and laying dense graded bituminous macadam using crushed aggregates of specified grading, premixed with VG30 grade bituminous binder and, transporting the hot mix to work site, laying to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10 complete in all respects complete as per specifications.. MORTH Specification No. 507 - using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-II (50 mm to 75 mm) with 4.5 % VG-30 Bitumen	cum	7544.53	Rupees Seven Thousand Five Hundred Forty Four And Paise Fifty Three Only
34	798.87	KSRRB M500-19. Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications. Clause 507 of MORTH V revision : using 40/60 TPH capacity H.M.P. with Mechanical Paver Gr-II (30 mm to 40 mm) with 5.4% VG-30 Bitumen	cum	8600.00	Rupees Eight Thousand Six Hundred Only
35	0.00	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete.	Nos	345.05	Rupees Three Hundred Forty Five And Paise Five Only
36	0.00	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.MORTH Chapter 8	Sqm	66.14	Rupees Sixty Six And Paise Fourteen Only
37	196.98	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. MORTH Specification No. 803 ---- Including all lead lifts loading unloading transportation labour hire charges of machinery curing for concrete works cost and convene of all material and all other such incidental charges necessary for successful completion of works as per the detailed technical specification and direction of Engineer in charge of this work		563.00	Rupees Five Hundred Sixty Three Only

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. R Lokesh	
				In figures	In words
38	306.00	KSRRB M800 Road markers I Road stud KSRRB MS00-35. Supply and Installtion of Moulded Shank Raised Pavement Markers made of polycarbonate and ABS(Acrylonitrile Butadiene Styrene) moulded body and reflective panels with micro prismatic lens capable of providing total internal reflection of the light entering the lens face and shall support a load of 16000 kg tested in accordance to Specifications of Category A of MORTH Circular No RW/ NH/33023/10-97- DO III Dt 11.06. 1997. The height, width and length shall not exceed 50 mm, 1DO mm and 102 mm and with minimum reflective area of 13 Sqcm on each side and the slope to the base shall be 35 degree. The strength of detachment of the integrated cylindrical shanks, (of diameter not less than 19 mm and height not less than 30 mm) from the body is to be a minimum value of 500 Kg. Fixing will be by drilling holes on the road for the shanks to go inside, without nails and using epoxy resin based adhesive as per manufacturer's recommendation and complete as directed by the engineer ---- Including all lead lifts loading unloading transportation labour hire charges of machinery curing for concrete works cost and convene of all material and all other such incidental charges necessary for successful completion of works as per the detailed technical specification and direction of Engineer in charge of this work		373.71	Rupees Three Hundred Seventy Three And Paise Seventy One Only
39	0.00	Supply and fixing of Retro Reflective Single arrow road name sign board of size 2000mm x 900mm made out of retro reflective sheeting conforming to Type XI standards of ASTM D 4956 - 09 & as per IRC 67-2012 for full back ground of blue colour & white letters and fixed over 4 mm thick Aluminium Composite Material sheet having minimum 0.5 mm thick Aluminium skin on both sides with back side painted grey colour and fixed over back support frame SS angle of 15mm x 20mm x 1.2mm, supported by 38mm OD stainless steel pipe all round in 304 grade and 2 nos of vertical posts of 50 mm OD stainless steel pipe of 202 grade firmly fixed to the ground by means of properly designed foundation of size 450mm x 450mm x 600mm in 1:1.5:3 ratio cement concrete. The background shall be blue in color with letters and border in white, the item includes earthwork excavation, cost of all materials, loading, unloading, lead, lift, transportation etc., complete. as per clause 6.9 of IRC 67-2012 for Type XI retro reflective sheeting from the sheeting manufacturer & a certified copy of test reports from an independent test laboratory conforming to clause 6.7 of IRC 67-2012 including outdoor weather exposure report for the retro reflective sheeting offered shall be submitted by the contractor for technical qualification in the tender.		29380.00	Rupees Twenty Nine Thousand Three Hundred Eighty Only
40	16157.29	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum including all lead and lift, transportation etc, complete as per Engineer incharge.	cum	70.72	Rupees Seventy And Paise Seventy Two Only
41	16157.29	Cost of Haulage Excluding Loading and Unloading Taking output 10 t load and lead 10 km = 100 t.km (V-III Page No.3, Item No.1.4 A of PWD SR 2021-22) Lead 8 Km	cum	66.55	Rupees Sixty Six And Paise Fifty Five Only
El-01	2.00	Spun pole 11.00 mtr long	No	16850.00	Rupees Sixteen Thousand Eight Hundred Fifty Only
El-02	2.00	Single pole Structure kit	Set	26734.00	Rupees Twenty Six Thousand Seven Hundred Thirty Four Only
El-03	8.00	11 KV Horizontal X Arms Galvanized Iron (GI)	Set	333.00	Rupees Three Hundred Thirty Three Only
El-04	6.00	11 KV , 5 KN Composite/ Polymeric pin Insulator (24 mm dia FRP Rod)	No	180.00	Rupees One Hundred Eighty Only
El-05	10.00	GI wire 10 SWG	Kg	66.78	Rupees Sixty Six And Paise Seventy Eight Only

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. R Lokesh	
				In figures	In words
J-06	20.00	Guy wire 7/10 SWG	Kg	65.14	Rupees Sixty Five And Paise Fourteen Only
El-07	30.00	PVC pipe 150mm dia	Mtrs	267.00	Rupees Two Hundred Sixty Seven Only
El-08	30.00	PVC bend 150mm dia	No	183.00	Rupees One Hundred Eighty Three Only
El-09	30.00	PVC Pipe (25mm dia)	Mtrs	25.00	Rupees Twenty Five Only
El-10	2.00	GOS 200A S/B	Set	7799.00	Rupees Seven Thousand Seven Hundred Ninety Nine Only
El-11	2.00	H frame set for GOS	Set	3724.00	Rupees Three Thousand Seven Hundred Twenty Four Only
El-12	2.00	9 KV 5KA Metal Oxide Ceramic type with ground Disconnector	Set/ 3 Nos	2358.00	Rupees Two Thousand Three Hundred Fifty Eight Only
El-13	2.00	11 KV Class, HG Fuse unit with solid core insulators	Set	882.00	Rupees Eight Hundred Eighty Two Only
El-14	4.00	Earthing materials pipe type for grounding as per Drawing No. BESCOM/GM/CP/154 & 34/ Dt: 04-07-2007	Set	1501.00	Rupees One Thousand Five Hundred One Only
El-15	2.00	Caution/ Danger board	No	146.00	Rupees One Hundred Forty Six Only
El-16	6.00	Alkathene tube 19mm dia and in coils	Coil	458.00	Rupees Four Hundred Fifty Eight Only
El-17	2.00	Anti climbing Device (12 mtrs/ 1 kg GI Barbed wire) Lumsum	Kg	76.00	Rupees Seventy Six Only
El-18	10.00	9 Mtrs long RCC Pole	No	6258.00	Rupees Six Thousand Two Hundred Fifty Eight Only
El-19	10.00	11 KV Horizontal X Arms- Galvanised Iron (GI)	Set	333.00	Rupees Three Hundred Thirty Three Only
El-20	10.00	HT ST Support	Nos	61.00	Rupees Sixty One Only
El-21	48.00	11 KV, 5KN Composite/ Polymeric Pin Insulator (24mm dia FRP Rod)	No	180.00	Rupees One Hundred Eighty Only
El-22	20.00	45 KN Disc Insulators	Nos	301.00	Rupees Three Hundred One Only
El-23	20.00	LT 4 Pin Cross arms	Nos	252.00	Rupees Two Hundred Fifty Two Only
El-24	20.00	LT 2 Pin Cross arms	Nos	115.00	Rupees One Hundred Fifteen Only
El-25	16.00	RCC Pole Clamps	Nos	71.00	Rupees Seventy One Only
El-26	80.00	1.1 KV Pin Insulators	No.	48.00	Rupees Forty Eight Only
El-27	20.00	No. 8 KN Strain Insulators	No.	16.00	Rupees Sixteen Only
El-28	0.80	Rabbit ACSR Conductor	Kmt	36497.00	Rupees Thirty Six Thousand Four Hundred Ninety Seven Only

Scanned by TapScanner

		Item Name	Unit	Approved Rates of Sri. R Lokesh	
				In figures	In words
		LT Aerial Bunched cable 3x95+1x70+1x16 Sqmm Street light (Insulated messenger Cum Neutral)	Kmtr	435622.00	Rupees Four Lakh(s) Thirty Five Thousand Six Hundred Twenty Two Only
	6.00	Piercing Connector Suitable for 16 Sqmm- 95 Sqmm AB cable- Service Connections	No	235.00	Rupees Two Hundred Thirty Five Only
	6.00	Suspension Clamp Assembly 16 to 70 mm (Excluding pole clamp & eye hook)	Sets	196.00	Rupees One Hundred Ninety Six Only
El-32	1.00	Universal Hook and Bolts & Nuts	No	314.00	Rupees Three Hundred Fourteen Only
El-33	2.00	Dead end Clamp / Anchor Clamp Assembly 16 to 70 Sqmm Bare Messenger	Sets	206.00	Rupees Two Hundred Six Only
El-34	1.00	Pole Clamp for HT/LT AB cable	Sets	103.00	Rupees One Hundred Three Only
El-35	0.16	240 Sqmm, 1.1 KV LT, XLPE or Heat resistant PVC insulated, PVC exuted inner seath armoured UG LT cable	KMtr	768443.00	Rupees Seven Lakh(s) Sixty Eight Thousand Four Hundred Forty Three Only
El-36	10.00	Epoxy Terminating Kit (Pothead) Suitable for 1.1 KV Class LT UG Cables 3.5 x 225 /240/ 300 Sqmm	Set	574.00	Rupees Five Hundred Seventy Four Only
El-37	2.00	Spun pole 11.00 mtr long	No	2503.00	Rupees Two Thousand Five Hundred Three Only
El-38	2.00	Single pole Structure kit	Set	2236.00	Rupees Two Thousand Two Hundred Thirty Six Only
El-39	8.00	11 KV Horizontal X Arms Galvanized Iron (GI)	Set	106.00	Rupees One Hundred Six Only
El-40	2.00	Pole base concreting 1:2:4	Each	730.00	Rupees Seven Hundred Thirty Only
El-41	2.00	Pole base concreting 1:2:4 (1000 x 1000x 2500mm)	Each	12177.00	Rupees Twelve Thousand One Hundred Seventy Seven Only
El-42	2.00	Coping 1:2:4 (as per actuals)	Each	1930.00	Rupees One Thousand Nine Hundred Thirty Only
El-43	2.00	GOS 200A S/B	Set	700.00	Rupees Seven Hundred Only
El-44	2.00	H frame set for GOS	Set	210.00	Rupees Two Hundred Ten Only
El-45	2.00	9 KV 5KA Metal Oxide Ceramic type with ground Disconnector	Set/ 3 Nos	78.00	Rupees Seventy Eight Only
El-46	2.00	11 KV Class, HG Fuse unit with solid core insulators	Set	155.00	Rupees One Hundred Fifty Five Only
El-47	4.00	Earthing materials pipe type for grounding as per Drawing No. BESCOM/GM/CP/154 & 34/ Dt: 04-07-2007	Set	503.00	Rupees Five Hundred Three Only
El-48	2.00	Caution/ Danger board	No	53.00	Rupees Fifty Three Only
El-49	2.00	Anti climbing Device (12 mtrs/ 1 kg GI Barbed wire) Lumsum	Kg	28.00	Rupees Twenty Eight Only
El-50	10.00	9 Mtrs long RCC Pole	No	1424.00	Rupees One Thousand Four Hundred Twenty Four Only
El-51	10.00	11 KV Horizontal X Arms- Galvanised Iron (GI)	Set	106.00	Rupees One Hundred Six Only
El-52	10.00	HT ST Support	Nos	64.00	Rupees Sixty Four Only
El-53	20.00	LT 4 Pin Cross arms	Nos	106.00	Rupees One Hundred Six Only

Scanned by TapScanner

		Item Name	Unit	Approved Rates of Sri. R Lokesh	
				In figures	In words
	0.60	LT 2 Pin Cross arms	Nos	106.00	Rupees One Hundred Six Only
		Rabbit ACSR Conductor	Kmt	2869.00	Rupees Two Thousand Eight Hundred Sixty Nine Only
El-56	0.20	LT Aerial Bunched cable 3x95+1x70+1x16 Sqmm Street light (Insulated messenger Cum Neutral)	Kmtr	22469.00	Rupees Twenty Two Thousand Four Hundred Sixty Nine Only
El-57	6.00	Piercing Connector Suitable for 16 Sqmm- 95 Sqmm AB cable- Service Connections	No	85.00	Rupees Eighty Five Only
El-58	6.00	Suspension Clamp Assembly 16 to 70 mm (Excluding pole clamp & eye hook)	Sets	127.00	Rupees One Hundred Twenty Seven Only
El-59	1.00	Universal Hook and Bolts & Nuts	No	169.00	Rupees One Hundred Sixty Nine Only
El-60	2.00	Dead end Clamp / Anchor Clamp Assembly 16 to 70 Sqmm Bare Messenger	Sets	127.00	Rupees One Hundred Twenty Seven Only
El-61	1.00	Pole Clamp for HT/LT AB cable	Sets	211.00	Rupees Two Hundred Eleven Only
El-62	10.00	Epoxy Terminating Kit (Pothead) Suitable for 1.1 KV Class LT UG Cables 3.5 x 225 /240/ 300 Sqmm	Set	1709.00	Rupees One Thousand Seven Hundred Nine Only
El-63	90.00	Cable trench excavation, 100x0.6x1-600 ordinary soil	Cumtr	226.00	Rupees Two Hundred Twenty Six Only
El-64	0.48	Laying of cable in trench LT cable	KMtr	20998.00	Rupees Twenty Thousand Nine Hundred Ninety Eight Only
El-65	90.00	Refilling & consolidation	Cumtr	50.00	Rupees Fifty Only

Executive Engineer
Project Division Yelahanka Zone

Scanned by TapScanner